

## Výkaz kubatur zemních prací

Objekt	výkop	výkop rýhy a jámy	podkladní vrstvy nestmelené	zemní krajnice	násyp + zásyp	zpětný zásyp rýh a jam	nakupovaný materiál	přebytek na skládku	sejmutí ornice	ohumusování svahů
	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>
SO 020									54	
SO 101	117	36	205	8	61+36		302	153		
SO 101.1	30	250	139	60	194	10	184	393		
SO 102	306	191	1 709	44	650+39		2 442	497		1 097
SO 102.1	23	28	211	93	96	8	400	43		
SO 110										
SO 116.1	3	7			6		6	10		
SO 116.2		7			6		6	7		
SO 135	3		32		3		35	3		
SO 180										
SO 201	88	702	673	25	105+558	8	688	782		
<b>Celkem</b>	<b>570</b>	<b>1 221</b>	<b>2 969</b>	<b>230</b>	<b>305</b>	<b>26</b>	<b>4 063</b>	<b>1 888</b>	<b>54</b>	<b>1 097</b>

## Výkaz kubatur vybouraných hmot

Objekt	živice vrstvy stmelené	podkladní vrstvy	svodidlo / zábradlí	směrové sloupky	potrubí / kamenná rovnanina	beton
	m <sup>3</sup>	m <sup>3</sup>	m	ks	m / m3	m <sup>3</sup>
SO 020			399 / 0	2	2 / 2	
SO 101	2	7				
SO 101.1	13	38	0 / 13		0 / 189	29
SO 102	59	233				
SO 102.1	9	27	56 / 0			7
SO 110						
SO 116.1						
SO 116.2						
SO 135	0.1	0.4				
SO 180						
SO 201	36	108	14 / 9		0 / 34	110
<b>Celkem</b>	<b>119</b>	<b>413</b>	<b>469 / 22</b>	<b>2</b>	<b>0 / 225</b>	<b>146</b>

## Výkaz kubatur - vyfrézovaný materiál

Objekt	frézování vozovek	použito na zpevnění krajnic a sjezdů	odvezeno na skládku
	m <sup>3</sup>	m <sup>3</sup>	m <sup>3</sup>
SO 020			
SO 101	174	88	86
SO 101.1	7		7
SO 102	411	163	248
SO 102.1	5		5
SO 110	11	3	8
SO 116.1			
SO 116.2	4	4	
SO 135			
SO 180			
SO 201	25	11	14
<b>Celkem</b>	<b>637</b>	<b>269</b>	<b>368</b>

